

APPROVED
 Date 11-16-93
CALHOUN COUNTY
REMONUMENTATION.

RECORDED

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

Nov 18 2 22 PM '93
 CLERK-REGISTER
 CALHOUN COUNTY, MICH.
 ANNE B. NORLANDER

For corners in

Calhoun Located In: Corner Code ##
 (County)
Battle Creek Township Section 26
 1. Public Land Survey T 2S R 8W K-11
 T _____ R _____
 T _____ R _____
 T _____ R _____
 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____
 4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Book 2 Page 651
 Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Daniel M. Ryan, in a field survey on November 16, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 Resurvey by Hodgeman, 1887±: April, 1979, Carroll Pike:
 Set by old survey of school done when Monument box in at Capital & Beckley.
 corner was existing. LCRC indicates as I-11.
 Maple 12" N44°W, 80 links May, 1972 - LCRC Book 1#49, DeKeyser
 Hickory 12", S69°E, 89 links 1" iron monument box.
 U.Pole - N45°E, 40.12 feet
 U.Pole - S35°E, 49.64 feet
 U-Pole - N55°W, 57.23 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Found monument box and 1" iron on intersection of the centerlines of Beckley Road and Capital Avenue.
 No witnesses from above.
 This corner has been used by local surveyors and is a good perpetuation of the original location.


SURVEY & REMONUMENTATION

OCT 27 1994

COMMISSION

LIBER 1716 PAGE 452

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Accepted 1" iron in monument box as a permanent and long-standing monument.
 Fire hydrant top not, N60°E, 78.40 feet
 U-pole, N45°W, 72.70 feet. Set nail & spotter.
 U-pole, S45°E, 67.70 feet. Set nail & spotter.
 U-pole, N30°E, 89.70 feet. Set nail & spotter.



Signed by Daniel M. Ryan Date November 16, 1993
 Surveyor's Michigan License No. 34975