

**SURVEY &
REMONUMENTATION**

APR 26 1995

APPROVED

Date 11-28-94
**CALHOUN COUNTY
REMONUMENTATION.**

CALHOUN COUNTY REMONUMENTATION
COMMISSION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Calhoun

(County) Battle Creek Twp	Located In:	Corner Code #
1. Public Land Survey	T <u>2</u> S R <u>8</u> W	<u>K-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

5 DEC 94 10:25 A.M.

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

I, Donald J. Davis, in a field survey on November 20, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original Survey in 1826 by Sylvester Sibley. Resurvey in 1887 by Hodgeman.
3" iron with cap in centerline of pavement used by DeKeyser in 1959.
3" iron with cap recorded in Book 1, page 50, in 1972.
Pipe removed in road construction, iron set in concrete monument box by City of Battle Creek.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" iron in monument box in Capital Avenue S.W.
Accepted as good preservation of original corner.

LIBER **1779** PAGE **374**

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" iron in concrete in monument box.
Nail & Tag Utility pole N 30° W 80.55'
Nail & Tag Utility pole S 30°W 70.20'
Nail & Tag 16" Maple N 70° E 36.40'
SW corner brick Apartment building S 60° E 115.35'



Signed by Donald J. Davis
Surveyor's Michigan License No. 17617

Date November 28, 1994