

**APPROVED**  
 Date 11-12-96  
**CALHOUN COUNTY**  
**REMONUMENTATION.**  
 For corners in

**CALHOUN COUNTY REMONUMENTATION**  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
 CALHOUN COUNTY  
 RECORDED

19 NOV 96 1:51 P.M.

ANNE B. NORLANDER  
 CLERK - REGISTER OF DEEDS

LIBER **1899** PAGE **595**

**SURVEY & REMONUMENTATION**  
 Register of Deeds Stamp & File Number

Calhoun (County) Located In: Corner Code #

**Battle Creek Twp**

1. Public Land Survey Sec 13 T 2 S R 8 W L-7  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

MAR 21 1997

COMMISSION

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Battle Creek

I, Robert R. Carr, in a field survey on November 11, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

1. G.L.O.; S. Sibley D.S. 1826.
2. Resurvey: F. Hodgeman 1887, corner dug out with road construction, set post from White Oak bearing tree.
3. C.F.C. (Clyde Chambers) no date; 1" iron stake in 1 ft concrete.
4. Plat of "Lakeshire Village" Liber 17 page 07.
5. Plat of "Chapel Hill Estates" Liber 13 page 12.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1" iron pipe in concrete base under bituminous surface 1.5 ft deep.  
 Verified location of iron pipe with monumentation in plats of "Lakeshire Village" and "Chapel Hill Estates".  
 Accepted iron pipe in concrete as faithful perpetuation of corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Broke concrete from iron pipe and placed Berntsen Calhoun County Remonumentation Monument in monument box over pipe.  
 Nail & spotter in Easterly side of U-Pole N05°W 226.60 feet.  
 Nail & spotter in Easterly side of U-Pole N32°E 65.61 feet.  
 Nail & spotter in Southerly side of U-Pole S80°E 131.74 feet.  
 Nail & spotter in Northerly side of U-Pole S87°W 14.19 feet.  
 SW corner of house foundation N71°E 82.37 feet.



Signed by Robert R. Carr  
 Surveyor's Michigan License No. 20704

Date November 12, 1996