

APPROVED

Date 2-2-94
CALHOUN COUNTY
REMONUMENTATION.

SURVEY &
REMONUMENTATION

OCT 27 1994

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

COLEMAN REGISTER
CALHOUN COUNTY, MICH.
ANNE B. NORLANDER
FEB 4 3 11 PM '94

RECORDED

For corners in

Calhoun Located In: _____ Corner Code # _____
(County)

1. Public Land Survey T 2 S R 8 W L-13
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Register of Deeds Stamp & File Number

I, William K. Crane in a field survey on December 3, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original Government Field Notes (1826):

Resurvey in 1887 of Battle Creek Township by F. Hodgman:

6" W. Oak N 81° E 104 links
6" W. Oak N 26° W 25 links

Corner obliterated. Set post 26 links West of the Leroy Corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found clay tile as described in resurvey notes and the following reference ties from "Peer Group" research provided by the Remonumentation Committee:

TILE

4" Hickory SW 3.89'
4" Hickory East 14.2'
Hickory SSE 45.1'
17' West of hedge row and in line with fence East and West
17' East of fence North

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced tile with standard Calhoun County remonumentation corner (Berntsen Monument)
Clay tile for North 1/4 Corner Section 1,
Leroy Twp., T3S, R8W:
East 17.05'
Fd. PK nail S. side 18" Apple: S 85° E 20.57'
Set nail W. side 24" Hickory: S 20° E 44.65'
Set nail N. side wood fc. post: West 7.55'
Fd. PK nail W. side wood fc. post: East 18.56'

LIBER 1730 PAGE 827

Signed by William K Crane

Date 1/27/94

Surveyor's Michigan License No. 29243

