

APPROVED

Date 11-12-96
CALHOUN COUNTY
REMONUMENTATION.

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

19 NOV 96 1:59 P.M.

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS

LIBER 1899 PAGE 614

Register of Deeds Stamp & File Number

Calhoun <small>(County)</small>	Located In:	Corner Code #
Albion Twp.		
1. Public Land Survey	T <u>3S</u> R <u>4W</u>	<u>E-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

I, Frederick J. Cutcher, in a field survey on October 28, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	10	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

Original Government Survey, February, ~~1824~~ 1825 W. Oak 7" S 29° E 30 lks.; B. Oak 9" S 51° W 191 lks. ~~(Mullett)~~ LYON F.C.
Surveyor Unknown, 2/81: 1" iron 2' N. of centerline; 20" oak S. 45° E. 44.61'; 12" Spruce S. 40° W. 37.4'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 60D spike at road surface from above witnesses. Dug down 12" and found 1" iron pipe.

Found both of above witnesses.

SURVEY &
REMONUMENTATION

MAR 21 1997

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Placed Berntsen monument in monument box over 1" iron pipe and is accepted as a careful and faithful reestablishment of the position of the original corner.

2' North of centerline.
In line with tree row to South.
Nail & spotter in North side of 18" Oak N 80° W 189.80'.
Nail & spotter in West side 30" Oak S 40° E 44.35'.
Nail & spotter in West side 24" Pine S 35° W 38.16'.
Nail & spotter in West side R.R. tie post S 20° E 40.54'.



Signed by Frederick J. Cutcher Date November 7, 1996
Surveyor's Michigan License No. 24592