

APPROVED

Date 10-21-97
**CALHOUN COUNTY
REMONUMENTATION.**

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

24 OCT 97 12:04 P.M.

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS

LIBER 1973 PAGE 187

Register of Deeds Stamp & File Number

For corners in

Calhoun County (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>3S</u> R <u>4W</u>	<u>G-9</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Frederick J.

I, Cutcher, in a field survey on 10/6, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

ALBION TWP.

A. Description of original monument and accessories and/or subsequent restoration:

Original Government Survey by Lyon, 1825: 7" B. Oak S. 23 1/2° W. 90 lks.; 18" W. Oak N. 41 1/2° E. 71 lks.

P. McPherson, August 1973: Iron; 28" Maple S. 80° W. 75.07'; 2" steel fnc. post North 19.15'; 28" Maple S. 09° W 117.0'; 14" Oak N. 55° E. 50.02'; Tele. station S. 51° E. 41.85'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

On 10-6-97 I found a 1/2" x 18" iron about in centerline intersection of 27 Mile Road and H Drive S.

Two witnesses were found.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced iron with Harrison and is accepted as best available evidence of the position of the original corner.

About in line with centerline of roads to South and East and West.
Center of chain link fence corner N. 2° W. 19.13'
S.W. cor. house N. 38° W. 78.30' to siding
Cen. 12" Maple S. 74° W. 135.8'
N.E. cor. house fdn. S. 48° W. 111.40'
Top cen. tel. stan. S. 50° E. 42.30'.



Signed by Frederick J. Cutcher
Surveyor's Michigan License No. Frederick J. Cutcher 24592

Date October 9, 1997

**SURVEY &
REMONUMENTATION**

APR 07 1998

SECTION