

APPROVED

Date 10-21-97
CALHOUN COUNTY
REMONUMENTATION.

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

24 OCT 97 12:03 P.M.

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS

LIBER 1973 PAGE 185

Register of Deeds Stamp & File Number

For corners in

Calhoun County (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>3S</u> R <u>4W</u>	<u>G-10</u>
	T ___ R ___	___
	T ___ R ___	___
	T ___ R ___	___
2. Property Controlling in Section	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___
	S ___ T ___ R ___	___

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Frederick J.

I, Cutcher, in a field survey on 10/6, 1997, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		10		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

ALBION TWP.

Original Government Survey by Lyon, 1825: 8" Bur Oak N. 30 1/2° W. 27 lks.; 7" Bur Oak S. 5° W. 19 lks.

P. McPherson, August, 1973: Iron; Cen. conc. post East 22.20'; face R.R. rail fnc. post West 26.42'; 6" Oak N. 41° W. 37.60'; 8" Oak N. 36° E. 34.60'; 5" Hickory S. 36° E. 42.38'.

F. Cutcher, June 1979 and June 1997: Found 1/2" dia. iron per above.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

On 10-6-97 I found a 1/2"x18" iron at road surface.

Five witnesses remain.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Replaced 1/2"x18" iron with Harrison and is accepted as the best available evidence of the position of the original corner.

In centerline of 27 Mile Road. In line with fence East and West.
Nail & spotter N. side Power Pole S. 86° W. 26.90'
Face of R.R. track anchor post N. 88° W. 26.35'
Face of conc. anchor post East 21.65'
Nail & spotter S.W. side 18" Hickory S. 32° E. 42.70'
Nail & spotter E. side 24" Oak N. 25° W. 62.58'.

Signed by Frederick J. Cutcher
Surveyor's Michigan License No. 24592

Date October 9, 1997

SURVEY &
REMONUMENTATION

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1985

APR 07 1998

SECTION