

APPROVED

Date 10-21-97
CALHOUN COUNTY
REMONUMENTATION.

CALHOUN COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

24 OCT 97 12:05 P.M.

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS

LIBER 1973 PAGE 188

Register of Deeds Stamp & File Number

For corners in

Calhoun County (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>3S</u> R <u>4W</u>	<u>G-11</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Frederick J.

I, Cutcher, in a field survey on 10/6/97, 19 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original Government Survey by Lyon, 1825: 18" W. Oak N. 5° E. 46 lks.; 18" W. Oak S. 85° W. 39 lks.

ALBION TWP.

P. McPherson, August 1973: Iron; 16" Maple N. 68° E. 45.90'; Twin 30" Cherry S. 61° E. 53.50'; Tel. station S. 38° E. 35.39'; 16" Oak N. 65° W. 93.04'; Fnc. South is West 5'; Face of 6" steel fnc. post N. 45° E. 39.08'

F. Cutcher, June 1979 and June 1997: Found 1/2" dia. iron per above.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

On 10-6-97 I found a 1/2" x 18" iron in centerline intersection of J Drive South and 27 Mile Road.

Five witnesses remain.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced 1/2" x 18" iron with Berntsen marker in monument box and is accepted as the best available evidence of the position of the original corner.

In centerline intersection of J Drive South and 27 Mile Road.

Face of steel cor. post N. 45° E. 38.95'
Cen. 12" Maple N. 27° W. 71.55'
S.W. corner house fdn. N. 35° W. 182.75'
Cen. 30" Oak N. 65° W. 93.2'
Nail & spotter S.E. side 18" Maple N. 70° E. 46.05'

Signed by Frederick J. Cutcher
Surveyor's Michigan License No. Frederick J. Cutcher 24592

Date October 97



SURVEY &
REMONUMENTATION

APR 07 1998

SECTION