

APPROVED

Date 10-21-97
CALHOUN COUNTY
REMONUMENTATION.

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

For corners in

| | | |
|---------------------------------------|-------------------------|----------------|
| <u>Calhoun County</u> (County) | Located In: | Corner Code #: |
| 1. Public Land Survey | T <u>3S</u> R <u>4W</u> | <u>H-9</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

24 OCT 97 12:04 P.M.

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS

LIBER 1973 PAGE 186

Register of Deeds Stamp & File Number

Frederick J.
Cutcher

I, Cutcher, in a field survey on October 6, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original Government Survey by Lyon, 1825: 11" Bur Oak S. 69° E. 18 lks.; 9" Bur Oak N. 11° E. 73 lks.

Max Walter, MSHD, 6/27/67: 3/4" iron pipe; Steel fence cor. North, 41.00'; 19" Oak N. 67° E. 85.65'; 29" Maple S. 01° E. 25.67'; 26" Maple S. 74° W. 89.22'; 36" Maple N. 71° W. 131.35'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

On 10-6-97 I found a 3/4" x 30" iron (pinch top) in centerline of H Drive S.

Three witnesses remain.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced pinch top iron with a Harrison and is accepted as the best available evidence of the position of the original corner.

In centerline of H Drive South
Face of Steel cor. post N. 2° W. 41.15'
Cen. 8" Maple N. 23° E. 28.30'
Cen. 8" Maple N. 60° E. 49.76'
Nail & spotter S.E. side 36" Oak N. 73° E. 85.75'
Cen. 4" Maple S. 53° E. 55.80'
Cen. 12" Oak N. 40° W. 46.30'

| A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | |
| 5 | | | | | | | | | | | | |
| 6 | 15 | 17 | 16 | 15 | 14 | 13 | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | |
| 13 | | | | | | | | | | | | |

ALBION TWP.

Signed by Frederick J. Cutcher
Surveyor's Michigan License No. 24592

Date October 9, 1997



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 20, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

SURVEY &
REMONUMENTATION

APR 07 1998

SECTION