

APPROVED
 late 11-12-96
CALHOUN COUNTY
REMONUMENTATION.
 For corners in

CALHOUN COUNTY
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
 CALHOUN COUNTY
 RECORDED

19 NOV 96 2:01 P.M.

ANNE B. NORLANDER
 CLERK - REGISTER OF DEEDS

LIBER 1899 PAGE 620

Register of Deeds Stamp & File Number

<u>CALHOUN</u> (County)	Located In:	Corner Code #
ALBION TWP.		
1. Public Land Survey	T 3 S R 4 W	I-1
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

ALBION TWP.

Frederick J. Cutcher in a field survey on November 2, 1996 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original Government Survey, 1824: Burr Oak 20" S 52-1/2° E 1.74 links; no other near.
 (Mullett) 1825
 LYON F.C.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found one 1 1/4" x 18" and one 1 1/4" x 48" iron pipes, one bent West and one bent East. They crossed at bottom of 18" pipe. Fits GLO 64 links West of Corner I-13, T2S, R4W, Sheridan.

No old witnesses were found.

**SURVEY &
 REMONUMENTATION**

MAR 21 1997

COMMISSION



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced iron pipes with Bernsten with 1 1/4" x 18" pipe inside and is accepted as a careful and faithful reestablishment of the position of the original corner.

Corner I-13, T2S, R4W is East 42.24' (64 links).
 Nail & spotter W. side util. pole S 10° E 40.23'.
 S.E. corner building #219 N 60° W 4.80'.
 W. edge of sidewalk is East 11.15'.
 N.E. corner building #219 N 5° W 28.57'.
 N.W. corner of Gas Co. Building S 75° E 138.50'.
 S.W. corner of end of conc. retaining wall N 65° E 87.44'.
 Top center fire hydrant N 15° E 112.10'.

Signed by Frederick J. Cutcher Date November 7, 1996
 Surveyor's Michigan License No. 24592