

APPROVED

Date 11-12-96

CALHOUN COUNTY  
REMONUMENTATION.

For corners in

|                                       |                           |               |
|---------------------------------------|---------------------------|---------------|
| <u>CALHOUN</u><br>(County)            | Located In:               | Corner Code # |
| ALBION TWP.                           |                           |               |
| 1. Public Land Survey                 | T <u>3</u> S R <u>4</u> W | <u>I-2</u>    |
|                                       | T _____ R _____           | _____         |
|                                       | T _____ R _____           | _____         |
|                                       | T _____ R _____           | _____         |
| 2. Property Controlling<br>in Section | S _____ T _____ R _____   | _____         |
|                                       | S _____ T _____ R _____   | _____         |
| 3. Miscellaneous<br>Property in Sec.  | S _____ T _____ R _____   | _____         |
|                                       | S _____ T _____ R _____   | _____         |
| 4. Lot No. _____, Recorded Plat _____ |                           |               |
| 5. Private Claims _____               |                           |               |

STATE OF MICHIGAN  
CALHOUN COUNTY  
RECORDED

19 NOV 96 2:01 P.M.

ANNE B. NORLANDER  
CLERK - REGISTER OF DEEDS

LIBER 1899 PAGE 621

Register of Deeds Stamp & File Number

Frederick J. Cutcher, in a field survey on October 29, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original Government Survey, 1825: Burr Oak 19" S 30° W 2.89 lks; Burr Oak 9" N 1° W 60.7 lks. (Lyon)

Surveyor & Date Unknown: Intersection of Eaton St. & N. line of Mechanics Addition (Irwin & Hodges Liber 2, Page 19). Corner house foundation S.W. 74'; Corner concrete porch N.W. 49.8'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 2" iron pipe in monument box. Monument box is 4" below pavement surface.

One of the above witnesses was found.

SURVEY &  
REMONUMENTATION

MAR 21 1997

COMMISSION

| A  | B  | C  | D  | E  | F  | G  | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |
| 6  | 16 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |

ALBION TWP.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 1/2" x 18" iron rod with cap #24592 in iron pipe and is accepted as a careful and faithful reestablishment of the position of the original corner.

S.W. corner house foundation #807 N 65° E 50.80'.  
S.E. corner house foundation #806 N 40° W 79.03'.  
S.E. corner house foundation #808 N 75° W 49.86'.  
Nail & spotter in E. side power pole N 25° E 46.13'.  
On North line of Irwin & Hodges Addition Liber 2, Page 19 of Plats.  
In centerline of S. Eaton Street.

Signed by Frederick J. Cutcher Date November 7, 1996  
Surveyor's Michigan License No. 24592

