

APPROVED

Date 10-21-97  
CALHOUN COUNTY  
REMONUMENTATION.

CALHOUN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
CALHOUN COUNTY  
RECORDED

24 OCT 97 12:02 P.M.

For corners in

<u>Calhoun County</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>3S</u> R <u>4W</u>	<u>I-9</u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
2. Property Controlling in Section	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
3. Miscellaneous Property in Sec.	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>

ANNE B. NORLANDER  
CLERK - REGISTER OF DEEDS

LIBER 1973 PAGE 181

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Frederick J. Cutcher, in a field survey on 10/6, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		10		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

ALBION TWP.

A. Description of original monument and accessories and/or subsequent restoration:

Original Government Survey by Lyon, 1825: 7" Bur Oak N. 10 1/2° E. 86 lks.; 7" Bur Oak N. 73 1/2° E. 48 lks.

Max Walter, MSHD, 6/26/67: 3/4" iron pipe over 1/2" rod; at intersection of M-99 & H Drive S; St. fe. cor. N. 43° W. 45.48'; 20" W. Cherry S. 45° E. 62.47'; 30" Maple S. 7° W. 71.80'; 31" Maple S. 61° W. 52.15'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

On 10-2-97 I found a pinch top iron in a Monument Box (center top of monument box is broken) in centerline intersection of M-99 and H Drive South.

Two witnesses remain.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I was unable to remove remainder of lid so used hole in top of lid to reference iron and is accepted as best available evidence of the position of the original corner.

Pinch top iron in monument box.  
In centerline intersection of M-99 and H Drive South.  
S.E. cor. R.R. track end post N. 40° W. 45.00'  
Nail & spotter W. side 24" Oak S. 25° E. 79.85'  
Nail & spotter in N. side 18" Maple S. 70° W. 81.65'  
Found nail & spotter E. side 30" Oak N. 13° W. 107.97'  
Found nail & spotter E. side 36" Maple S. 30° W. 71.80'

Signed by Frederick J. Cutcher  
Surveyor's Michigan License No. 24592

Date October 9, 1997



REMONUMENTATION

APR 07 1998

SECTION