

APPROVED

Date 10-21-97
CALHOUN COUNTY
REMONUMENTATION.

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

For corners in

Calhoun County (County)	Located In:	Corner Code #
1. Public Land Survey	T3S R4W	I-10
	T R	
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous	S T R	
Property in Sec.	S T R	

24 OCT 97 12:02 P.M.

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS

LIBER 1973 PAGE 183

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Frederick J. Cutcher in a field survey on 10/2, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		11		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original Government Survey by Lyon, 1825: 20" W. Oak S. 52½° W. 55 lks.; 19" Bur Oak N. 16° W. 26 lks.

Max Walter, MSHD, 6/26/67: Iron bolt in centerline of M-99; 31" Maple S. 79° E. 41.22'; 21" Oak S. 49° W. 29.42'; 45" Oak S. 89° W. 33.50'; 20" Oak N. 38° W. 42.12'.

F. Cutcher, 1985: Found monument box.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

On 10-2-97 I found a monument box in the centerline of M-99 in line with fence to West; in line with field line to East. No iron was in Monument Box.

Four witnesses remain.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Dug down to 18" and hit large rock or concrete. Cut off bottom of Berntsen marker and set in center of existing monument box and is accepted as best available evidence of the position of the original corner.

In centerline of M-99.

P.K. S. side 8" dia. post anchored to 42" Oak West 31.30'

Nail & spotter N. side 24" Oak S. 55° W. 29.32'

Nail & spotter N.E. side 24" Oak N. 38° W. 41.97'

Nail & spotter S. side 8" dia. post N. 68° E. 40.25'

Signed by Frederick J. Cutcher
Surveyor's Michigan License No. 24592

Date October 9, 1997



SURVEY &
REMONUMENTATION

APR 07 1998

SECTION

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1985