

APPROVED

Date 10-21-97
CALHOUN COUNTY
REMONUMENTATION.

CALHOUN COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

24 OCT 97 12:02 P.M.

For corners in

Calhoun County (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>3S</u> R <u>4W</u>	<u>I-11</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

ANNE D. NORLANDER
CLERK - REGISTER OF DEEDS

LIBER 1973 PAGE 182

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Frederick J.

I, Cutcher, in a field survey on 10/2, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4			3		2	1
3													
4	7			8			9			10		11	12
5													
6	18			17			16			15		14	13
7													
8	19			20			21			22		23	24
9													
10	30			29			28			27		26	25
11													
12	31			32			33			34		35	36
13													

ALBION TWP.

A. Description of original monument and accessories and/or subsequent restoration:

Original Government Survey by Lyon, 1825: 18" W. Oak S. 42° E. 1.07 lks.; 17" Bur Oak N. 2 1/2° E. 79 lks.

Max Walter, MSHD, 6/26/67: 3/4" iron rod at intersection of M-99 & J Drive S.; 34" Oak N. 47° W. 39.52'; 21" Hickory N. 64° E. 53.55'; 19" Hickory S. 68° E. 63.10'; N.E. cor. conc. pillar S. 56° W. 39.04'.

F. Cutcher, April 1985: Found monument box.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

On 10-2-97 I found a monument box in the centerline intersection of M-99 and J Drive S. Monument box had no iron in it.

Three witnesses remain.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I dug down to 15" and hit rock or concrete. Cut off Berntsen marker and set in center of monument box and is accepted as best available evidence of the position of the original corner.

In centerline intersection of M-99 and J Drive S.
Found nail & spotter N.W. side 24" Hickory N. 63° E. 54.45'
Found nail & spotter N. side 24" Hickory S. 70° E. 63.68'
N.E. cor. (face) conc. post S. 57° W. 38.05'
Top cen. tel. stan. N. 43° E. 48.25'

Signed by Frederick J. Cutcher
Surveyor's Michigan License No. Frederick J. Cutcher 24592

Date October 9, 1997



SURVEY &
REMONUMENTATION

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1985

APR 07 1998

SECTION