

APPROVED

Date 9-15-99 RRL
CALHOUN COUNTY
REMONUMENTATION.
 For corners in

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
 CALHOUN COUNTY
 RECORDED

29 SEP 1999 10:31:23 AM

ANNE B. NORLANDER
 CLERK - REGISTER OF DEEDS

LIBER **2164** PAGE **715**

Register of Deeds Stamp & File Number

<u>CALHOUN</u> (County)	Located in:	Corner Code #
ALBION TWP	T <u>3S</u> R <u>4W</u>	<u>M-10</u>
1. Public Land Survey	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Michael A. Groat, in a field survey on August 17, 1999, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6												
3													
4	7												
5													
6	10												
7													
8	19												
9													
10	30												
11													
12	31												
13													

A. Description of original monument and accessories and/or subsequent restoration:


ORIGINAL SURVEY, 1825, LUCIUS LYON, DEPUTY SURVEYOR, SET POST.
 BURR OAK, 5° S 89 W, 64 LINKS, BURR OAK, 8°, S 51° W, 64 LINKS.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND IRON IN CENTERLINE OF ROAD, IN LINE WITH FENCE WEST. EXCAVATED AND FOUND ANOTHER 1/2" IRON BENEATH FOUND NOTHING ELSE. ACCEPTED THIS POSITION AS THE BEST AVAILABLE EVIDENCE OF THE ORIGINAL CORNER SET BY LYON.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET A BERNTSEN MONUMENT IN MONUMENT BOX.
 NAIL & TAG IN 12" BURR OAK, SOUTH 56° WEST, 40.17 FEET
 NAIL & TAG IN 15" CHERRY, NORTH 30° WEST, 51.17 FEET
 NAIL & TAG IN 15" SHINGLE OAK, NORTH 26° EAST, 59.36 FEET
 NAIL & TAG IN 15" WHITE OAK, SOUTH 09° EAST, 99.38 FEET.



Signed by [Signature]

Date September 13, 1999

Surveyor's Michigan License No. 39079

SURVEY &
 REMONUMENTATION

MAR 13 2000

SECTION