

APPROVED

Date 9-15-99 RRC

CALHOUN COUNTY  
REMONUMENTATION.

CALHOUN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
CALHOUN COUNTY  
RECORDED

29 SEP 1999 10:31:58 AM

ANNE B. NORLANDER  
CLERK - REGISTER OF DEEDS

LIBER 2164 PAGE 717

Register of Deeds Stamp & File Number

For corners in

CALHOUN  
(County)

Located In:

Corner Code #

ALBION TWP  
1. Public Land Survey

T3S R4W  
T\_\_\_ R\_\_\_  
T\_\_\_ R\_\_\_  
T\_\_\_ R\_\_\_  
S\_\_\_ T\_\_\_ R\_\_\_  
S\_\_\_ T\_\_\_ R\_\_\_  
S\_\_\_ T\_\_\_ R\_\_\_  
S\_\_\_ T\_\_\_ R\_\_\_

M-11

SURVEY &  
REMONUMENTATION

MAR 13 2000

2. Property Controlling  
in Section  
3. Miscellaneous  
Property in Sec.

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

SECTION \_\_\_\_\_

I, Michael A. Groat, in a field survey on August 17, 1999, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

ORIGINAL SURVEY, 1825 BY LUCIUS LYON DEPUTY SURVEYOR, SET POST, 8" BURR OAK, NORTH 5° WEST, 104 LINKS, 5" BURR OAK, SOUTH 34° WEST, 32 LINKS NO DATE, T.P.J, LARGE BLUE ROCK, SET 1" PIPE OVER, IN LINE WITH CENTERLINE OF ROAD WEST, 2' WEST OF CENTERLINE NORTH AND SOUTH, FACE OF 10" CONC. POST, SOUTH 45° WEST, 43.50', 12" OAK, NORTH 45° WEST, 48.70'; 24" OAK, NORTH 30° EAST, 77.60'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" IRON OVER 1 1/2" PIPE, BENEATH BOTH IS A LARGE BLUE ROCK. CHECK WITH WITNESSES FROM T.P.J. ACCEPTED THE LOCATION OF THE BLUE ROCK AS A CAREFUL & FAITHFUL PERPETUATION OF THE ORIGINAL MONUMENT.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET BERNTSEN MONUMENT, IN MONUMENT BOX IN PLACE OF THE IRON. F.D. P.K. NAIL IN 20" BURR OAK, N 40° W, 46.43 FEET FACE OF CONC. FENCE POST, S 40° W, 53.00 FEET F.D. P.K. NAIL, 15" WHITE OAK, S 50° E, 47.10 FEET SET NAIL IN 10" SHINGLE OAK, N 74° E, 69.60 FEET.

Signed by [Signature]  
Surveyor's Michigan License No. 39079

Date September 13, 1999



FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1979  
REVISED JAN. 1983  
REVISED OCT., 1988