

**SURVEY &  
REMONUMENTATION**

MAR 2 1 1997

CALHOUN COUNTY REMONUMENTATION  
**LAND CORNER RECORDATION CERTIFICATE COMMISSION**  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
CALHOUN COUNTY  
RECORDED

24 SEP 96 11:00 A.M.

ANNE B. NORLANDER  
CLERK - REGISTER OF DEEDS

Register of Deeds Stamp & File Number

**APPROVED**  
Date SEPT 18 1996  
**CALHOUN COUNTY  
REMONUMENTATION.**  
For corners in

Calhoun <small>(County)</small>	Located In:	Corner Code #:
Eckford Township		
1. Public Land Survey	T <u>3</u> S R <u>5</u> W	C-1
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, William K. Crane, in a field survey on September 13, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Eckford Township

A. Description of original monument and accessories and/or subsequent restoration:

Original Government Survey,  
Lucius Lyon, 1825:

Intersected North boundary 59 links  
West of Post

34" W. Oak      S5°E      29 links  
22" D.O.      S48°W      40 links

Corner recorded by Dekeyser & Associates in 1972,  
in Liber 1007, Page 67:

Set corner 38.94' West of S.E. Corner, Section 31,  
Marengo Township

1.65' West of North and South fence  
0.4' North of fence East

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" iron and witnesses per LCRC, Liber 1007, Page 67.

0.4' North of East and West fence  
1.65' West of North and South fence

LIBER 1887 PAGE 980

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced 1/2" iron with standard Calhoun County Remonumentation Monument (Berntsen Monument).

S.E. Corner, Section 31, Marengo Twp.	East	38.94'
18" Maple	North	3.34'
12" Elm	South	36.11'
16" Cherry	West	41.72'

This is accepted as the best available evidence of the position of the original corner.



Signed by William K. Crane Date September 18, 1996  
Surveyor's Michigan License No. 29243