

MAR 30 1999

APPROVED

Date 7-15-98 *RLC*

CALHOUN COUNTY
REMONUMENTATION.

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

20 JUL 1998 1:53:17 PM

For corners in

<u>Calhoun</u> (County)	Located In:	Corner Code #
Eckford		
1. Public Land Survey	T <u>3S</u> R <u>5W</u>	<u>G-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS
LIBER **2044** PAGE **153**

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Michael A. Groat, in a field survey on July 9, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

ORIGINAL SURVEY BY LUCIUS LYON, DEPUTY SURVEYOR, 1825, SET POST, B. ASH, 12", N 51 DEGREES E, 9 LINKS; R. OAK, 14", N 76 DEGREES W, 40 LINKS COURTRIGHT, 1895, ELM 22", N 70-1/2 DEGREES E, 107-1/2 LKS; 38 LINKS WEST OF CLARENDON CORNER. S.W. OAK, 9", S 34 DEGREES E, 45 LINKS FRED CUTCHER, P.S., FOUND IRON 8" BELOW ROAD; 14' WEST OF FENCE SOUTH FENCE CORNER POST, S 20 DEGREES E, 34.6'; FACE OF 30" OAK, S 60 DEGREES E, 53.8'; FACE OF 10" OAK, N 54 DEGREES E, 40.2'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND PLOW POINT 8" DOWN & BIG ROCK. BROKEN PIECES OF TILE ALSO. CHECKED WITH SOME WITNESSES FROM ABOVE. ACCEPTED THE POSITION OF THE PLOW POINT AS THE BEST EVIDENCE OF THE ORIGINAL CORNER. SET BERNTSEN MONUMENT WITH MONUMENT BOX.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

THE CORNER IS A BERNTSEN MONUMENT WITH CORNER INFORMATION AND P.S. # STAMPED IN BRASS CAP.

NAIL & TAG IN EASTERLY SIDE OF 30" OAK, 11 DEGREES NAZ, 61.07'
NAIL & TAG IN SOUTHERLY SIDE OF 20" OAK, 59 DEGREES NAZ, 41.71'
NAIL & TAG IN WESTERLY SIDE OF 15" HICKORY, 150 DEGREES NAZ, 37.66'
NAIL & TAG IN WESTERLY SIDE OF 36" OAK, 123 DEGREES NAZ, 54.25'

NOTE: NAZ=MAGNETIC AZIMUTH MEASURED FROM NORTH



Signed by *Michael A. Groat*
Surveyor's Michigan License No. 39079

Date 7-9-98