

MAR 30 1999

SECTION

APPROVED

Date 12-9-98 KAC  
CALHOUN COUNTY  
REMONUMENTATION.

CALHOUN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
CALHOUN COUNTY  
RECORDED

For corners in

<u>Calhoun</u> (County)	Located In:	Corner Code #
Eckford		
1. Public Land Survey	T <u>3S</u> R <u>5W</u>	<u>H-13</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

15 DEC 1998 3:36:43 PM

ANNE B. NORLANDER  
CLERK - REGISTER OF DEEDS

LIBER **2087** PAGE **931**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Michael A. Groat, in a field survey on December 8, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

ORIGINAL SURVEY BY LUCIUS LYON, DEPUTY SURVEYOR, 1825, SET POST, HICKORY 9", N 75 DEGREES E, 18 LKS; ELM 10", N 45 W, 26 LKS, 1883 COUNTY SURVEYOR, SET POST AT 40.08 CHAINS; W. ASH, 8", N 60 DEGREES E, 51 LKS. CAROL PIKE, P.S., JANUARY, 1974, RAIL ROAD SPIKE, 2' NORTH OF CENTERLINE; 22" HICKORY, N 60 DEGREES E, 79.49'; 18" HICKORY, N 55 E, 48.32'; 10' EAST OF FENCE NORTH 16.4' WEST OF FENCE SOUTH FRED CUTCHER, P.S., FOUND RAILROAD SPIKE, 2' NORTH OF CENTERLINE; 12.6' WEST OF FENCE SOUTH; (FACE) 18" HICKORY, N 70 DEGREES W, 79.2'; (FACE) 12" MAPLE, S 20 DEGREES E, 45.3'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND RAIL ROAD SPIKE 2' NORTH OF CENTERLINE AS CALLED FOR ABOVE. THIS LOCATION DOES NOT MATCH ANY OCCUPATION NOR FIT THE SPLIT, WHICH IS HOW THE COUNTY SURVEYOR SET IT IN 1883. IF MID-WAY ON LINE IS HELD, THE LOCATION MATCHES THE FENCE RUNNING NORTH AND THE CENTERLINE OF A ROAD RUNNING NORTH A 1/4 MILE WEST. EXCAVATION WAS MADE AT THE R.R. SPIKE AND NOTHING ELSE WAS FOUND. OTHER CORNERS IN THIS AREA HAD PIPE AND CROCKERY AROUND THEM. SINCE IT CANNOT BE DETERMINED HOW THE R.R. SPIKE GOT THERE, IT WAS NOT HELD. SET A NEW CORNER MID-WAY ON LINE.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

THE CORNER IS A BERNTSEN MONUMENT WITH CORNER CODE INFORMATION AND P.S. #39079 STAMPED IN THE BRASS CAP. WITNESSES  
4' NORTH OF CENTERLINE  
SET NAIL & TAG IN SOUTHERLY SIDE OF A 10" MAPLE, 20° NAZ, 52.63'  
SET NAIL & TAG IN WESTERLY SIDE OF A 6" OAK, 150° NAZ, 44.85'  
SET NAIL & TAG IN SOUTHERLY SIDE OF A 8" HICKORY, 200° NAZ, 50.20'  
FOUND NAIL IN 24" HICKORY, 290° NAZ, 67.35'

NOTE: NAZ=MAGNETIC AZIMUTH MEASURED FROM NORTH



Signed by [Signature]

Date December 9, 1998

Surveyor's Michigan License No. 39079