

APPROVED

Date 8-17-94
CALHOUN COUNTY
REMONUMENTATION.

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

18 AUG 94 12:14 P.M.

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS

For corners in

CALHOUN (County)	Located In:	Corner Code #
ECKFORD TWP		
1. Public Land Survey	T 3 S R 5 W	K-3
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, ROBERT R. CARR, in a field survey on JUNE 3, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

ORIGINAL CORNER SET BY DEPUTY SURVEYOR LYON 1826
-SURVEY BY COUNTY SURVEYOR B.F. WELLS 1879
IRON PIPE AND BRICKS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3" X 3" X 12" WHITE GRANITE STONE WITH BRICKS
REPLACED GRANITE STONE WITH BERNTSEN MONUMENT AND MONUMENT BOX

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

BERNTSEN MONUMENT
NAIL & SPOTTER SOUTHERLY SIDE 14" MAPLE N65°E 62.43 FT.
NAIL & SPOTTER NORTHERLY SIDE TWIN 12" OAK N65°W 109.40 FT.
NAIL & SPOTTER NORTHERLY SIDE 14" MAPLE S70°W 77.82 FT.
NAIL & SPOTTER NORTHWESETRLY SIDE 18" HICKORY S36°W 68.21 FT.

SURVEY &
REMONUMENTATION

OCT 24 1994

COMMISSION

LIBER 1763 PAGE 773



Signed by [Signature]
ROBERT R. CARR 20704
Surveyor's Michigan License No. _____

Date AUGUST 16, 1994