

APPROVED

Date 8-17-94
CALHOUN COUNTY
REMONUMENTATION.

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>CALHOUN</u> (County)	Located In:	Corner Code #
ECKFORD TWP		
1. Public Land Survey	T <u>3</u> S R <u>5</u> W	K-4
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

18 AUG 94 12:14 P.M.

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, ROBERT R. CARR, in a field survey on JUNE 3, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

ORIGINAL CORNER SET BY DEPUTY SURVEYOR LYON 1826
SURVEY BY COUNTY SURVEYOR B.F. WELLS
FOUND DECAYED STAKE & G.L.O WITNESSES STUMP 1879
PIN OAK 11" N74-1/4°W 57 FT
MAPLE 3" S85-1/2°E 42 FT
WITNESS TO RAILROAD SPIKE BY C.W. PIKE 1973
24" WALNUT N40°W 61.84 FT
28" OAK S40°E 51.63 FT 3 FT± EAST OF CENTERLINE OF NORTH/SOUTH ROAD
IN LINE WITH EAST/WEST FENCE

SURVEY &
REMONUMENTATION
OCT 24 1994
COMMISSION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND RAILROAD SPIKE 4 FT± EAST OF CENTERLINE OF NORTH/SOUTH ROAD IN LINE WITH EAST/WEST FENCE
FOUND 24" WALNUT & 28" OAK (WITNESSES 1973)
CUT 3' X 4' HOLE IN BIT SURFACE & DUG FOR EVIDENCE OF PREVIOUS RESTORATION, FINDING NONE
ACCEPTED RAILROAD SPIKE AS PERPETUATION OF CORNER
REPLACED RAILROAD SPIKE WITH BERNTSEN MONUMENT IN MONUMENT BOX

LIBER 1763 PAGE 772

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

BERNTSEN MONUMENT
NAIL & SPOTTER WESTERLY SIDE 40" OAK S27°E 52.33 FT
NAIL & SPOTTER WESTERLY SIDE 10" MAPLE S88°W 32.48 FT
NAIL & SPOTTER EASTERLY SIDE 36" WALNUT N28°W 62.08 FT
SOUTHWEST CORNER HOUSE N76°E 107.23 FT
RAILROAD POST S85°E 25.69 FT. IN LINE WITH FENCE
TO EAST/WEST .4'± EAST OF CENTERLINE OF NORTH/SOUTH ROAD



Signed by Robert R. Carr
Surveyor's Michigan License No. 20704

Date AUGUST 16, 1994