

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

APPROVED
 Date Nov. 20 1995
CALHOUN COUNTY
REMONUMENTATION.
 STATE OF MICHIGAN
 CALHOUN COUNTY,
 RECORDED

4 DEC 95 2:22 P.M.

ANNE B. NORLANDER
 CLERK - REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in

<u>Calhoun</u> (County)	Located In:	Corner Code #:
<u>Eckford Township</u>		
1. Public Land Survey	T <u>3</u> S R <u>5</u> W	<u>L-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, William K. Crane, in a field survey on February 7, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original Survey 1825, Lucius Lyon:

9" Hickory S 77° E 73 links
 24" W. Oak N 84-3/4° W 162 links

B.F. Welles, April 12, 1880:

Found bottom of both witnesses and put in a marble 3 x 3, 18" long.
 Stone wall, 52 links North to nearest side.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" rered fitting occupaton. No other previous witnesses were left. Accepted as corner location.

REMONUMENTATION

LIBER **1834** PAGE **248**

FEB 22 1996

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced 1/2" rered with standard Calhoun County Remonumentation Corner (Bernsten Monument) in a monument box.

20" Hickory S 10° W 28.20'
 6" Maple N 30° W 45.53'
 6" Maple N 15° E 33.22'
 5" Birch S 80° E 61.58'

Centerline of
 Bit. Road North 2' ±
 Fence to North East 2' ±

This is accepted as the best available evidence of the position of the original corner.

Signed by William K. Crane

Date November 20, 1995

Surveyor's Michigan License No. 29243

