

# APPROVED

Date 12/10/99 RRC  
**CALHOUN COUNTY**  
**REMONUMENTATION.**

**CALHOUN COUNTY REMONUMENTATION**  
**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN  
 CALHOUN COUNTY  
 RECORDED

For corners in  
 Fredonia Township  
 Calhoun County

Located In: Corner Code #

1. Public Land Survey	T	_____	R	_____	_____		
	T	_____	R	_____	_____		
	T	_____	R	_____	_____		
	T	_____	R	_____	_____		
2. Property Controlling In Section	S	<u>4</u>	T	<u>3S</u>	R	<u>6W</u>	F-2
	S	_____	T	_____	R	_____	_____
3. Miscellaneous Property in Sec.	S	_____	T	_____	R	_____	_____
	S	_____	T	_____	R	_____	_____

17 DEC 1999 2:33:20 PM

ANNE B. NORLANDER  
 CLERK - REGISTER OF DEEDS

LIBER **2185** PAGE **990**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Scott E. Koch, in a field survey on November 11, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Degree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

A. Description of original monument and accessories and/or subsequent restoration:

Original Corner not set by GLO Survey.

May 9, 1998 - Scott E. Koch, PS #41103,  
 In an unrecorded survey by Ledy Survey Group, Project No. 98.0649,  
 calls for a Found 1/2" Rebar, but gives no witnesses. It does show a  
 distance of 2646.76' to G-2, and a distance of 2642.14' to F-3.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5			●		3		2			1
3													
4	7		8		9			10		11			12
5													
6	18		17		16			15		14			13
7													
8	19		20		21			22		23			24
9													
10	30		29		28			27		26			25
11													
12	31		32		33			34		35			36
13													

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Searched at the apparent location of the corner and found a 1/2" Iron, 1.3± South of the painted centerline of "A" Drive South, and 2.5± East of a Tree row to the South. Dug to a depth of 3± and found no additional evidence of the corner. 1/2" Iron lies 1.02 feet South & 2.38 feet East of intersection of 1/4 lines. Accepted 1/2" Iron as the best available evidence of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced 1/2" Iron with Standard Berntsen Monument stamped Calhoun Co. Remon. & PS 41103 in Monument Box.  
 Set Nail & Tag in SW'ly face of Twin 20" Cherry, S60°E, 60.15'  
 Set Nail & Tag in E'ly face of 5" Red Oak, Due South, 25.68'  
 Set Nail & Tag in S'ly face of Utility Pole, N60°E, 102.59'  
 Set Nail & Tag in S'ly face of Utility Pole, N60°W, 98.45'

SURVEY &  
 REMONUMENTATION

MAR 13 2000

SECTION



Signed by Scott E. Koch

Date November 16, 1999

Surveyor's Michigan License No. 41103