

MAR 30 1999

APPROVED

Date 12-9-98 *rrc*
CALHOUN COUNTY
REMONUMENTATION.

SECTION
CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

For corners in

CALHOUN _____ (County)	Located In:	Corner Code #
FREDONIA	T <u>3S</u> R <u>6W</u>	<u>G-4</u>
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling In Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

15 DEC 1998 3:37:06 PM

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS

LIBER **2087** PAGE **933**

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Michael A. Groat, in a field survey on August, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9	6	10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

1825, LUCIUS LYON, DEPUTY SURVEYOR, SET POST, W. OAK, 16", S 8 1/2° W, 18 LKS,
W. OAK, 7", N 38° E, 32 LKS.
C. PIKE, P.S., 1976, 1" IRON PIPE AT THE INTERSECTION OF FENCES, 22" HICKORY, NORTH,
1.90'; TWIN HICKORY, N 65° E, 35.15'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

FOUND 1" PIPE AT INTERSECTION OF FENCES. ACCEPTED THE PIPE AS THE BEST EVIDENCE OF THE ORIGINAL MONUMENT.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET A BERNTSEN MONUMENT IN PLACE OF THE PIPE
NAIL & TAG IN 24" HICKORY, NORTH, 2.00'
NAIL & TAG IN 20" CHERRY, S 70° W, 14.29'
NAIL & TAG IN 10" CHERRY, S 10° W, 20.84'
NAIL & TAG IN 20" HICKORY, N 66° E, 41.45'
CARSONITE MARKER SET 1.0' SOUTH.



Signed by *Michael A. Groat*
Surveyor's Michigan License No. 39079

Date December 4, 1998