

MAR 30 1999

APPROVED

Date 10-29-98 RLC
CALHOUN COUNTY
REMONUMENTATION.

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

29 OCT 1998 2:41:57 PM

For corners in

<u>Calhoun</u> (County)	Located In:	Corner Code #
Fredonia	T <u>3S</u> R <u>6W</u>	<u>G-6</u>
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

ANNE D. MORLANDER
CLERK - REGISTER OF DEEDS
LIBER 2073 PAGE 285

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		16		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Michael A. Groat, in a field survey on October 8, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

ORIGINAL SURVEY BY LUCIUS LYON IN 1825, SET POST, 10" TAM, S 87° E, 3.94 LKS,
W. OAK, 9° N 1/4° W, 10.47 LKS.
DON DAVIS, 1981, SET PIPE IN ROCKS, 7.3' NORTH OF FENCE WEST, 40" WILLOW, WEST 22'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND PIPE IN ROCKS AS CALLED FOR BY DAVIS. MEASURES 2658.5' NORTH OF CORNER TO THE SOUTH & 2654.96' SOUTH OF CORNER TO THE NORTH. SET BERNTSEN MONUMENT IN PLACE OF PIPE.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

BERNTSEN MONUMENT WITH CARSONITE MARKER 1' SOUTH
NAIL & TAG IN 10" MAPLE, S 50° W, 34.60'
NAIL & TAG IN 6" OAK, S 42° W, 40.55'
NAIL & TAG IN 24" OAK, S 45° E, 57.50'
NAIL & TAG IN 15" HICKORY, N 43° E, 63.95'
6' NORTH OF ROW OF WILLOW TREES
1.3' SW OF FENCE CORNER



Signed by [Signature]
Surveyor's Michigan License No. 39079

Date October 8, 1998