

APPROVED

Date 5-19-99 RLC
CALHOUN COUNTY
REMONUMENTATION.

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

14 JUN 1999 1:58:03 PM

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS

LIBER **2134** PAGE **499**

Register of Deeds Stamp & File Number

For corners in

Located in:	Corner Code #
Calhoun (County) Fredonia Township 1. Public Land Survey	T <u>3S</u> R <u>6W</u> <u>H-11</u>
	T _____ R _____
	T _____ R _____
	T _____ R _____
2. Property Controlling in Section	S _____ T _____ R _____
	S _____ T _____ R _____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____
	S _____ T _____ R _____
4. Lot No. _____, Recorded Plat _____	
5. Private Claims _____	

I, William K. Crane, in a field survey on April 16, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	16		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. Lucius Lyon, 1825:
9" Beech N 62° E 9 links
11" D. O. N 30° W 20 links

MSHD, Holmes, 1963:
Found original wooden stake, replaced with 1" iron pipe.
21" Oak N 07° E 20.78'
22" Maple S 77° W 55.22'
19" Oak S 30° E 39.64'

C.D. Pike, 1972:
Iron N 26.9'
Center of concrete fence post S 05° E 35.55'
8" Shag Bark Hickory S 30° E 40.15'
20" Oak N 26.68'
1' North of centerline E & W gravel road

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found 1" pipe in rocks on centerline of E & W gravel road. Replaced with Harrison monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Standard Calhoun County Remonumentation monument (Harrison monument) and is accepted as a perpetuation of the position of the original

corner.
Set nail and tag in 26" Red Oak S 30° E 39.22'
Set nail and tag in 12" Hickory S 35.15'
Set nail and tag in 10" Hickory S 40° W 49.43'
South face of 12" concrete fence corner N 26.68'

Signed by William K. Crane Date 5/19/99
William K. Crane, P.S.

Surveyor's Michigan License No. 29243

SURVEY &
REMONUMENTATION

MAR 13 2000

SECTION

