

MAR 30 1999

APPROVED

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

Date 7-15-98 *MAL*
CALHOUN COUNTY
REMONUMENTATION.

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

20 JUL 1998 1:53:29 PM

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS

LIBER **2044** PAGE **154**

Register of Deeds Stamp & File Number

For corners in

Calhoun _____ (County)	Located In:	Corner Code #
FREDONIA	T 3S R 6W	1-3
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Michael A. Groat, in a field survey on September, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
Original Survey by Lucius Lyon, Deputy Surveyor, 1825, Set post, Tamarack, 10", N 30°W, 9.5 LKS, Tamarack, 10", S 73°W, 1-12 LKS

F.K. Holmes, 10/63, found cedar post in bed of drainage ditch. N 45° W, 31" Maple, 30.52', N 15° E, 13" Ash, 51.03', East, 5" Maple, 26.95'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found an iron on E'ly side of Silted Drainage ditch. Checked into the remaining witnesses from Holmes. Accepted the Location of this iron as the best perpetuation of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set a bermtsen monument with the section information stamped in the Brass cap.
Nail & Tag in S'ly side of 8" Maple, East, 17.23'
Nail & Tag in W'ly side of Group of Maples, 155° NAZ, 35.15'
Nail & Tag in E'ly side of 20" Maple, 352° NAZ, 50.4'
Nail & Tag in N'ly side of 8" Maple, West, 21.2'

NAZ: Magnetic Azimuth measured from north

Signed by *MAL*
Surveyor's Michigan License No. 39079

Date May 21, 1998

