

**SURVEY &  
REMONUMENTATION**

MAR 1 8 2000

**APPROVED**

Date 5-19-99 *KRC*  
**CALHOUN COUNTY  
REMONUMENTATION.**

**SECTION**

**CALHOUN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN  
CALHOUN COUNTY  
RECORDED

14 JUN 1999 1:57:14 PM

For corners in

<u>Calhoun</u> (County)	Located In:	Corner Code #
Fredonia Township		
1. Public Land Survey	T <u>3S</u> R <u>6W</u>	<u>I-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

ANNE B. NORLANDER  
CLERK - REGISTER OF DEEDS

LIRER **2134** PAGE **496**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, William K. Crane, in a field survey on April 17, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. Lucius Lyon, 1825:

9" W. Oak S 27° E 44 links  
20" D. O. N 18° E 82 links

G. Lewis, 1882:

Large stone

MSHD, Holmes, 1963:

After interview with property owners, crew dug trench along East-West section line fence and found decayed post that is accepted as the corner. Raised with 3/4" iron pipe, Centennial Farm tenant claim post replaced original pointed stone.

27" Oak S 85° W 44.97'  
22" Maple S 85° E 49.40'  
25" Oak S 13.04'

C.D. Pike, 1972:

Found iron  
29" Oak W 44.97'  
24" Maple S 85° E 49.40'  
27" Oak S 13.04'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" pipe surrounded by rocks in old fence East and West. Replaced with Berntsen monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Standard Calhoun County Remonumentation monument (Berntsen monument) and is accepted as the best available evidence of the position of the original corner.

Set nail and tag in 36" Oak S 12.35'  
Set nail and tag in 14" Oak W 22.33'  
Set nail and tag in 20" Oak S 45° E 60.10'  
Set nail and tag in 24" Oak S 40° W 49.41'  
264' +/- East of I-69 R/W fence

Signed by William K. Crane

Date 5/19/99

William K. Crane, P.S.

Surveyor's Michigan License No. 29243

