

APPROVED

Date 8-17-94
CALHOUN COUNTY
REMONUMENTATION.

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

18 AUG 94 12:08 P.M.

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS

For corners in

Calhoun

(County)

Located In:

Corner Code #

1. Public Land Survey

T 3 S R 7 W

A-3

T _____ R _____

T _____ R _____

T _____ R _____

2. Property Controlling
in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous
Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Register of Deeds Stamp & File Number

I, Donald J. Davis, in a field survey on August 10, 1994

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Tile set in resurvey of 1885 by Gifford.

Pipe and bricks set over tile.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found pipe and bricks over tile pieces.

Accepted as good preservation of resurvey corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Berntsen monument in monument box at corner.

Nail & Tag 30" Maple S 35° W 82.28'

Nail & Tag Utility Pole N 80° E 68.90'

Nail & Tag Utility Pole N 30° W 52.61'

Nail & Tag 18" Sycamore S 30° E 74.82'

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

SURVEY &
REMONUMENTATION

OCT 24 1994

COMMISSION

LIBER 1763 PAGE 757

Signed by

Donald J. Davis

Date August 17, 1994

Surveyor's Michigan License No. 17617

