

APPROVED

Date 11-17-96
CALHOUN COUNTY
REMONUMENTATION.

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

19 FEB 97 3:49 P.M.

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS

LIDER 1916 PAGE 110

Register of Deeds Stamp & File Number

Calhoun (County) Newton Twp.	Located In:	Corner Code #
1. Public Land Survey	T <u>3S</u> R <u>7W</u>	<u>E-6</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Donald J. Davis, in a field survey on October 8, 1996,
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
current manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
Court of Law; established, re-established, monumented, re-monumented, recovered, found as
expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded
on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:
Original survey in 1826 by Sibley.
Resurvey by Whitney in 1897, tile set.
Survey by A.H. Chase in 1912 used tile to survey parcels.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Road construction buried corner.
Found corners of parcel to north and used to reset corner location.
Accepted as good perpetuation of corner location.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Set Berntsen monument in monument box, 3.5' East of centerline of road.
Face of bottom of 12" Concrete post East 23.65'
Nail & Tag 14" Spruce N 40° E 37.62'
Nail & Tag 30" Oak N 30° W 59.07'
Nail & Tag 12" Cherry West 40.10'
Nail & Tag 12" Hickory S 45° W 35.04'

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Newton Twp.



Signed by Donald J. Davis Date 2/3/97
Surveyor's Michigan License No. 17617

SURVEY &
REMONUMENTATION

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 29, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

APR 07 1998

SECTION