

APPROVED

Date 2-2-94
CALHOUN COUNTY
REMONUMENTATION.

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Calhoun
(County)

Located In:	Corner Code #
T 3S R 7W	F-9
T _____ R _____	_____
T _____ R _____	_____
T _____ R _____	_____
T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____

- Public Land Survey
- Property Controlling in Section
- Miscellaneous Property in Sec.
- Lot No. _____, Recorded Plat _____
- Private Claims _____

FEB 4 3 12 PM '94
 CLERK-REGISTER
 CALHOUN COUNTY, MICH.
 ANNIE B. MORLANDER

RECORDED

Register of Deeds Stamp & File Number

I, Michael A. Groat, in a field survey on January 12, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Re-Survey	T.P.J. unknown date	C.D. Pike 11-6-68
Tile	Iron over pipe	Iron
14" Elm, S85°W, 741ks	Fence East & West, 7' North	P.P., N60°E, 34'
	Iron East, 33.0'	P.P., N75°E, 77.8'
	U.P., S70°E, 27.4'	13' West of old C.R.R. bed
		32.1' East of fence South
		13' South of fence West

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Iron and checked with Pike witnesses:
 U.P., N60°E, 34'
 U.P., N75°E, 77.8'
 13' South of Fence West
 32.1' East of Fence South

SURVEY & REMONUMENTATION

OCT 27 1994

COMMISSION LIBER 1730 PAGE 833

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set standard Calhoun County Monument (Harrison)
 Witnesses:
 Nail with spotter in U.P. N55°E, 35.45'
 Nail with spotter in U.P. N75°E, 78.4'
 Nail with spotter in 6" Oak, N60°W, 30.6'
 Nail with spotter in 6" Oak, N35°W, 26.3'



Signed by Michael A. Groat Date 2-2-94
 Surveyor's Michigan License No. 39079