

APPROVED

Date 4-20-94
CALHOUN COUNTY
REMONUMENTATION.

CALHOUN COUNTY REMONUNANTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
CALHOUN
(County)

Located In: Corner Code #

- 1. Public Land Survey T 3S R 7W F-11
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

22 APR 94 4:54 P.M.
Register of Deeds Stamp & File Number

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, MICHAEL A. GROAT, in a field survey on April 2, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Re-Survey Gifford-1885	T.P.J.
Found of witness stump	5/8" Iron 15.5' South of C.L.
Set post from which:	U.P. South 10.35'
5" Poplar, S 82° W, 200 lks.	Fence North and South

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 5/8" Iron, 15.5' South of Centerline. Corner falls mid-way on line between Southeast and Southwest corners. Big fill area, swamp on both side of road. Tile long since has been gone. Held as a good perpetuation of corner.

SURVEY &
REMONUMENTATION

LIBER 1743 PAGE 406

OCT 27 1994

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Harrison Monument in place of iron
NAIL AND SPOTTER in U.P., South 10.1'
NAIL AND SPOTTER in U.P., North 45° East, 63.8;
Directly under power line
Centerline of Road, North 15.3 feet

Signed by Michael A. Groat

Date 4-20-94

Surveyor's Michigan License No. _____