

APPROVED

Date 2-2-94
CALHOUN COUNTY
REMONUMENTATION.

CALHOUN COUNTY MICHIGAN
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
CALHOUN
(County)

Located In: Corner Code #

- 1. Public Land Survey T 3S R 7W G-11
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____
Property in Sec. S _____ T _____ R _____

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

CLERK-REGISTER
CALHOUN COUNTY, MICH.
ANNE B. NORLANDER

FEB 4 3 12 PM '94

RECORDED

Register of Deeds Stamp & File Number

I, Michael A. Groat, in a field survey on January 13, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Re-Survey	Hollow Tile
Tile	28" Maple, N14°E, 28.4'
6" Hickory, S5°E, 63 lks	18" Hickory, S3°W, 35.05'
	10" W.O., S58°E, 47.2'
	19" Y.O., S41°E, 42.3'

1977, T.P.S.
5/8" Iron
30" Oak, S45°E, 43.25'
18" Hickory, South, 36.5'
6" Hickory, N80°W, 57.9'

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 5/8" Iron in pavement and witnesses:
30" Oak, S45°E, 43.25'
24" Hickory, S03°W, 36.5'

SURVEY &
REMONUMENTATION

OCT 27 1994

COMMISSIONER

LIBER 1730 PAGE 836

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set standard Calhoun County Monument (Berntsen) and monument box. Stamped license number 39079 and corner info.

Witnesses:
32" Oak, S45°E, 43.5'
24" Hickory, S03°W, 36.2'
24" Oak, S45°W, 52.7'
8" Maple, N30°E, 22.85'



Signed by Michael A. Groat

Date 2-2-94

Surveyor's Michigan License No. 39079