

APPROVED

Date 4-20-94
CALHOUN COUNTY
REMONUMENTATION.

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
CALHOUN
(County)

Located In:

Corner Code H-11

- | | | | | | |
|------------------------------------|---|-----------|---|-----------|-------------|
| 1. Public Land Survey | T | <u>3S</u> | R | <u>7W</u> | <u>H-11</u> |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous Property in Sec. | S | | T | R | |
| | S | | T | R | |
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

22 APR 94 4:54 P.M.

Register of Deeds Stamp
CLERK - REGISTER OF DEEDS

I, MICHAEL A. GROAT in a field survey on April 2, 19 94

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

Re-Survey Gifford-1885	1977 Gertz
18" Yellow Oak S 73 W, 13.3 Lks	5/8" Iron C.L. Road
18" Yellow Oak, S 58 1/2 E 68 Lks	30" Oak, N 71° E 71.7'
	24" Hickory S 72° E 75'
	24.5' South of Fence North

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 5/8" Iron in C.L. of road and checked to 1977 witnesses.
Held this as the corner.

SURVEY &
REMONUMENTATION

LIBER 1743 PAGE 405

OCT 27 1994

COMMISSIONER

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Bertsen monument and Monument Box

NAIL AND SPOTTER in 24" Oak, N 25° E 28.75'
 NAIL AND SPOTTER in 8" Oak N 60° W 55.45'
 NAIL AND SPOTTER in 36" Oak N 70° E 99.74
 NAIL AND SPOTTER in 24" Oak S 65° E 74.20'



Signed by

Michael A. Groat

Date

4-20-94

Surveyor's Michigan License No. _____