

APPROVED

Date 2-2-94 *MAA*

CALHOUN COUNTY REMONUMENTATION.

CALHOUN COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Calhoun (County)

Located In:

Corner Code #

- 1. Public Land Survey T 3S R 7W I-9
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

CLERK-REGISTER CALHOUN COUNTY MICHIGAN ANNIE B. NORTON ANDERSON

FEB 4 3 12 PM '94

RECORDED

Register of Deeds Stamp & File Number

- 4. Lot No. Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13. A dot is marked at row 9, column I.

I, Michael A. Groat, in a field survey on December 11, 1993

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Re-Survey 1922 Comp. Davis 1987
Set open tile Found tile in fences Found iron 3' NW of tile
4" triple Hickory, North 20' 20" Hickory, East, 170 lks Used tile
8" twin Hickory, NW 11.4' 12" Hickory, N5°E, 93 lks
10" twin Hickory, N85°W, 31.7' corner post, N85°E, 1.8'
3" pear, SE 34' 1992 J. Miller Found Iron
Fence Post North 8.85'
6" Elm, N20°E, 15.74'
12" twin Maple, N35°W 13.47' (Not corner)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: Found Iron from Miller witnesses and measured 3' SW, dug and found hollow tile

SURVEY & REMONUMENTATION

OCT 27 1994

LIBER 1730 PAGE 843

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Berntsen Monument over tile and stamped license #39079 and corner information in top. Set 6' carsonite marker beside.
Nail and spotter in 8" Oak, South 15.3'
Nail and spotter in 8" Ash, S85°E, 33.1'
Nail and spotter in 12" twin Maple, N35°W, 20.6'
Nail and spotter in 18" twin Maple, N80°W, 31.8'



Signed by Michael A. Groat

Date 2-2-94

Surveyor's Michigan License No. 39079