

APPROVED

Date 2-2-94  
CALHOUN COUNTY  
REMONUMENTATION.

CALHOUN COUNTY REMOUNTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

CLERK-REGISTER  
CALHOUN COUNTY, MICH.  
ANNE B. MORLANDER

FEB 4 3 12 PM '94

RECORDED

For corners in

Calhoun

(County)

Located In:

Corner Code ##

- |                                    |   |           |   |           |             |
|------------------------------------|---|-----------|---|-----------|-------------|
| 1. Public Land Survey              | T | <u>3S</u> | R | <u>7W</u> | <u>I-11</u> |
|                                    | T |           | R |           |             |
|                                    | T |           | R |           |             |
|                                    | T |           | R |           |             |
| 2. Property Controlling in Section | S |           | T | R         |             |
|                                    | S |           | T | R         |             |
| 3. Miscellaneous Property in Sec.  | S |           | T | R         |             |
|                                    | S |           | T | R         |             |
4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Michael A. Groat, in a field survey on January 12, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- |                                     |                          |
|-------------------------------------|--------------------------|
| Don Davis 1977                      | J. Miller 1992           |
| Iron and Rock, Broken Tile          | Iron in farm lane        |
| 18" Square Conc. Post, North 18.5'  | 2'x2' conc. post, S85°W, |
| 18" Square Conc. Post, S80°W, 20.2' | 18.6'                    |
|                                     | 2'x2' conc. post, North  |
|                                     | 18.6'                    |
|                                     | R.R. tie, South, 18.81'  |
|                                     | R.R. tie, East, 26.4'    |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Iron Next to Rock, dug and found remains of tile. Checked into J. Miller's witnesses from 1992.

SURVEY &  
REMONUMENTATION

OCT 27 1994

COMMISSION


LIBER 1730 PAGE 842

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Berntsen monument in place of tile. Stamped license #39079 and corner information in top and set 6' carsonite marker beside.

Witnesses:

- Face of 2'x2' conc. post, North 18.5'
- Face of 2'x2' conc. post, S80°W, 20.2'
- Nail with spotter in R.R. tie East 26.40'
- Nail with spotter in R.R. tie South 18.81'



Signed by Michael A. Groat Date \_\_\_\_\_

Surveyor's Michigan License No. 39079