

APPROVED

Date 6-15-94 DJD
CALHOUN COUNTY
REMONUMENTATION.
For corners in

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Calhoun (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>3</u> S R <u>8</u> W	<u>A-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED
16 JUN 94 9:08 A.M.

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Donald J. Davis, in a field survey on August 12, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner Post established by U.S. Government Deputy Surveyor Clark in 1826.

- 19 Links South of corner for T3S, R9W.
- 7" Beech N 56° E 23½ links
- 5" Lynn S 5½° E 34 links.

LIBER 1753 PAGE 721

Resurvey of 1885 tile set by Hodgman.

- 24" Elm S 12° E 31 links.
- 20" Elm S 68° W 49 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Original corner and accessories not recovered.

Found ^{solid} clay tile with X on top and stone around and is accepted as a careful and faithful perpetuation of the original corners position. Placed 20" Harrison Monument above solid clay tile with X on top and placed monument box over corner.

SURVEY &
REMONUMENTATION


OCT 24 1994

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-9, Corner of Sections 19 & 30, T3S-R8W.

- S.E. Cor Sec 24, T3S,-R9W, Harrison Monument above tile in Monument Box North 12.06'
- Center North End 30" CMP N 3° E 33.72'
- Center/Top Project Marker S 7° E 19.23'
- Set P.K. Nail in 11" Ash S 80° E 61.64'



signed by Donald J. Davis Donald J. Davis Date February 8, 1994

Surveyor's Michigan License No. 17617