

MAR 30 1999

APPROVED

Date 12-9-98 KRL
CALHOUN COUNTY
REMONUMENTATION.

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

15 DEC 1998 3:41:19 PM

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS

LIBER 2087 PAGE 947

Register of Deeds Stamp & File Number

For corners in

<u>CALHOUN</u>	Located In:	Corner Code #
(County)		
LEREOY TOWNSHIP		
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 18 T 3S R 8W	B-6
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, ROBERT R. CARR, in a field survey on OCTOBER 26, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

CENTER OF SECTION 18

A. Description of original monument and accessories and/or subsequent restoration:

THIS CORNER WAS NOT SET WITH ORIGINAL GOVERNMENT SURVEY AND WAS NOT ESTABLISHED BY HODGMAN WITH 1885 RESURVEY.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND CONCRETE MONUMENT 2655.89 FEET SOUTH OF NORTH 1/4 POST, SECTION 18.

MONUMENT IS 8" BELOW SURFACE AND IN GOOD SHAPE. LEFT MONUMENT IN PLACE AND INSTALLED MONUMENT BOX OVER CONCRETE MONUMENT.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

CONCRETE MONUMENT IN MONUMENT BOX
7' ± WEST OF CENTERLINE OF N&S ROAD
4' ± NORTH OF CENTERLINE OF ROAD TO WEST
8" WOOD CORNER POST, N30°W 41.50 FEET (SET SPOTTER)
3" STEEL CORNER POST, EAST 37.88 FEET
UTILITY POLE, S15°W 124.20 FEET (SET SPOTTER)
2655.89 FEET SOUTH OF NORTH 1/4 POST OF SECTION 18

THIS POSITION NOT ESTABLISHED BY ORIGINAL GOVERNMENT SURVEYORS.
THIS MONUMENT IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE CORNER.

Signed by [Signature]
Surveyor's Michigan License No. 20704 ROBERT R. CARR

Date DECEMBER 8, 1998

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

