

MAR 30 1999

APPROVED

Date 12-9-98 REC
**CALHOUN COUNTY
REMONUMENTATION.**

**CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

For corners in

<u>CALHOUN</u> (County)	Located In:	Corner Code #
LERROY TOWNSHIP		
1. Public Land Survey	T <u>3S</u> R <u>8W</u>	<u>E-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

15 DEC 1998 3:39:48 PM

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS

LIBER **2087** PAGE **939**

Register of Deeds Stamp & File Number

I, ROBERT R. CARR, in a field survey on JULY 15, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

CORNER COMMON TO SECTIONS 16, 17, 20 AND 21

A. Description of original monument and accessories and/or subsequent restoration:

ORIGINAL CORNER SET BY ROBERT CLARK, D.S.1826.

HODGMAN, RESURVEY 1885, FOUND STAKE IN MARSH AT INTERSECTION OF FENCES, NO WITNESSES, SET POST (TILE) NO WITNESS TREES NEAR.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND RING OF LARGE STONES IN WAIST DEEP WATER, AREA IS FLOODED BY BEAVERS. RING OF STONES IS 8' ± NORTHEASTERLY OF A R.R. TIE POST, 2692.63 FEET WEST OF THE NORTH 1/4 POST (GLO = 2674.32) AND 2647.17 FEET NORTH OF WEST 1/4 POST.

ACCEPTED RING OF STONES AS BEST EVIDENCE OF CORNER AND PLACED A 2" DIA. X8' PIPE IN RING OF STONES WITH BERNTSEN MONUMENT OVER AND CARSONITE WITNESS POST BESIDE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

BERNTSEN MONUMENT OVER 2"X8' PIPE IN RING OF STONES IN WAIST DEEP WATER SET CARSONITE POST ON NORTHEASTERLY SIDE
8" OAK, N07°W 59.45 FEET (SET SPOTTER)
5" HICKORY, N70°W 87.80 FEET (SET SPOTTER)
R.R. TIE POST, S80 ± °W 8.25 FEET
NORTH 1/4 POST, S88°58'57"W (ASSUMED BEARING) 2692.63 FEET
WEST 1/4 POST, S00°00'00"W (ASSUMED BEARING) 2647.17 FEET

AND IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3													
4	7			8		9		10		11		12	
5													
6	18			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													

Signed by [Signature]
Surveyor's Michigan License No. 20704 ROBERT R. CARR

Date DECEMBER 7, 1998

