

APPROVED

Date 12-9-98 RRC  
CALHOUN COUNTY  
REMONUMENTATION

CALHOUN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
CALHOUN COUNTY  
RECORDED

For corners in

Calhoun (County)	Located In:	Corner Code #
Leroy Township		
1. Public Land Survey	T <u>3</u> S R <u>8</u> W	<u>E-9</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

15 DEC 1998 3:33:40 PM

ANNE B. NORLANDER  
CLERK - REGISTER OF DEEDS

LIBER **2087** PAGE **922**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, William K. Crane, in a field survey on December 2 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		6		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

GLO Robert Clark, 1826:

6" W. Oak	N 77½° W	76 links
6" W. Oak	S 64½° E	10½ links

Resurvey, Hodgman, 1895:

Found stone with brick around and stake hole under. Set post with brick and stone around.  
Southeast corner of church N 37° W 100 links  
2" Maple North 64½ links

Gertz, 1983:

Set RR spike using adjacent section corners found and old resurvey notes. 3.3' North of marked centerline and 8" West of fence line North.  
Southeast corner of church N 36° W 67.7'  
30" Maple S 18° E 36.52'  
30" Maple S 51° W 52.58'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found RR spike over tile, bricks and stones as described above and 4½ North of painted centerline.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced tile with standard Calhoun County Remonumentation monument (Berntsen monument with monument box) and is accepted as a perpetuation of the position of the original corner.

Nail and tag in 24" Maple	S 45° E	52.70'
Nail and tag in 30" Maple	S 60° W	53.10'
Nail and tag in 28" Maple	N 70° W	120.54'
Nail and tag in 12" Maple	S 70° E	118.74'

Signed by William K. Crane  
William K. Crane, P.S.

Date December 9, 1998

Surveyor's Michigan License No. 29243

