

APPROVED

Date 12-9-98 MLL
CALHOUN COUNTY
REMONUMENTATION.

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
 CALHOUN COUNTY
 RECORDED

15 DEC 1998 3:33:27 PM

ANNE D. NORLANDER
 CLERK - REGISTER OF DEEDS

LIBER **2087** PAGE **921**

Register of Deeds Stamp & File Number

For corners in

<u>Calhoun</u> (County)	Located In:	Corner Code #
Leroy Township	<u>T.3 S. R.8 W.</u>	<u>E-10</u>
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, William K. Crane, in a field survey on November 23, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

GLO Robert Clark, 1826:
 12" Tamarack S 67° W 30 links
 11" Tamarack S 35° E 26 links

Resurvey Hodgman, 1885:
 Found stake standing in swamp N 35° W, 26 links from stump of bearing tree. Set post.
 6" Tamarack S 45° W 9½ links
 3" Tamarack N 10° W 11 links

SURVEY &
 REMONUMENTATION

MAR 30 1999

SECTION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Computed location midway between NW corner of Section 28 and SW corner of Section 28. Dug and probed extensively in a 15'± diameter area. Found no evidence of tile. May have been excavated for a 10' wide drainage ditch lying East of corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set standard Calhoun County Remonumentation monument (Bemtsen monument with a Carsonite marker) midway and on line.
 6.5'± West of North and South fence

Nail and tag in 10" Cherry	South	28.40'
Nail and tag in 10" Cherry	South	36.05'
Nail and tag in 20" Dead elm	North	12.54'
Steel fence post	East	6.48'

Signed by William K. Crane
 William K. Crane, P.S.
 Surveyor's Michigan License No. 29243

Date December 9, 1998

