

APPROVED

Date 12-9-98 RAL  
CALHOUN COUNTY  
REMONUMENTATION.

CALHOUN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
CALHOUN COUNTY  
RECORDED

15 DEC 1998 3:33:52 PM

For corners in

Calhoun	Located In:	Corner Code #
(County)		
Leroy Township		
1. Public Land Survey	T <u>3</u> S R <u>8</u> W	<u>E-11</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

ANNE B. NORLANDER  
CLERK - REGISTER OF DEEDS  
LIBER **2087** PAGE **923**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_ Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, William K. Crane, in a field survey on November 23, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO Robert Clark, 1826:

9" B. Ash	N 66° E	25 links
16" B. Ash	S 79° W	26 links

Resurvey, Hodgman, 1885:

Found old stake S 66° W, 25 links from U.S. bearing tree. Set post with brick under.

10" Elm	Northeast	13½ links
10" Elm	Southwest	11 links

Gertz, 1983:

Found clay tile 5' West of North and South fence, and 5' South of East and West fence.

Triple Ash	S 10° E	28.0'
11" Maple	S 5° W	18.4'
24" Maple	S 45° W	42.0'

Davis, no date:

Tile and "T" iron fence post

6" Maple	S 25° E	15.2'
24" Maple	S 50° W	41.6'

8' West of fence intersection

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found tile as described above.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced tile with standard Calhoun County Remonumentation monument (Berntsen monument with a Carsonite marker) and is accepted as a perpetuation of the location of the original corner.

Nail and tag in 40" Ash	N 60° W	30.03'
Nail and tag in 36" Maple	N 45° E	20.23'
Nail and tag in 30" Triple ash	S 25° E	27.85'
Nail and tag in 16" Twin maple	S 60° E	41.45'

Signed by William K. Crane

Date December 9, 1998

William K. Crane, P.S.

Surveyor's Michigan License No. 29243

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

SURVEY &  
REMONUMENTATION

MAR 30 1999

SECTION

