

SURVEY & REMONUMENTATION

1993

COMMISSION

**CALHOUN COUNTY
REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

CALHOUN

(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>3</u> S R <u>8</u> W	F-5
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

CLERK-REGISTRAR
 CALHOUN COUNTY, MICHIGAN
 ANNE B. MOORE, CLERK

SEP 1 10 32 AM '93

RECORDED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

DONALD J. DAVIS, in a field survey on JULY 23, 1993

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

1. Description of original monument and accessories and/or subsequent restoration:

CONCRETE POST OVER TILE & STONE ON POST WITH DRILL HOLE.

- 12" BURR OAK NW 41.45'
- 6" HICKORY NE 31.14'
- 8" HICKORY NE 43.14'
- 12" MAPLE S 70° E 96.25'
- 12" MAPLE S 20° E 91.28'
- 14" OAK SW 42.95'

TILE SET IN RESURVEY OF 1885.
 5" IRONWOOD N 66°E 5 LINKS
 6" IRONWOOD S 73°W 7 LINKS

3. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" IRON OVER DRILL HOLE IN STONE OVER CONCRETE POST BRINGING POINT TO ROAD SURFACE.
 FACE OF 22" OAK N 51° W 41.37'
 FACE OF 10" HICKORY N 38° E 30.80'
 FACE OF 13" HICKORY N 58° E 42.89'

THIS CORNER ACCEPTED AS A FAITHFUL PERPETUATION OF THE ORIGINAL CORNER AS RECORDED IN LIBER 1007, PAGE 69, CALHOUN COUNTY RECORDS.

2. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET BERNSTEIN STAINLESS STEEL MONUMENT WITH BRONZE CAP IN MONUMENT BOX AT CORNER.
 POWER POLE S 35° W 65.70' NAIL & SPOTTER
 POWER POLE S 20° E 62.15' NAIL & SPOTTER
 14" BURR OAK N 50° W 42.50' NAIL & SPOTTER
 12" HICKORY N 60° E 43.45' NAIL & SPOTTER
 CENTERLINES OF ROADS E, W, S.



Signed by Donald J. Davis
 Surveyor's Michigan License No. 17617

Date August 12, 1993