

MAR 30 1999

APPROVED

Date 12-9-98 REC  
CALHOUN COUNTY  
REMONUMENTATION.

CALHOUN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
CALHOUN COUNTY  
RECORDED

For corners in

15 DEC 1998 3:39:59 PM

ANNE D. NORLANDER  
CLERK - REGISTER OF DEEDS

LIBER 2087 PAGE 940

CALHOUN (County)	Located In:	Corner Code #
LEROY TOWNSHIP		
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>21</u> T <u>3S</u> R <u>8W</u>	<u>F-8</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, ROBERT R. CARR, in a field survey on JULY 16, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

CENTER, SECTION 21

A. Description of original monument and accessories and/or subsequent restoration:

THIS CORNER WAS NOT SET WITH ORIGINAL SURVEY AND WAS NOT ESTABLISHED WITH RESURVEY BY HODGMAN IN 1885.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5			4		3		2		1	
3													
4	7		8			9		10		11		12	
5													
6	18		17			16		15		14		13	
7													
8	19		20			21		22		23		24	
9													
10	30		29			28		27		26		25	
11													
12	31		32			33		34		35		36	
13													

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" IRON AT OCCUPATION OF CENTER. ESTABLISHED 1/4 CORNERS AND RAN 1/4 LINES AND FOUND 1/2" IRON TO BE 0.14 FEET NORTH AND 0.32 FEET WEST OF TRUE INTERSECTION.

ACCEPTED 1/2" IRON AS CENTER AND REPLACED SAME WITH BERNTSEN MONUMENT IN MONUMENT BOX.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

BERNTSEN MONUMENT IN MONUMENT BOX  
10" SQUARE CONCRETE POST, N84°W 33.38 FEET  
18" OAK, S28°W 57.24 FEET ( SET SPOTTER )  
10" HICKORY, S65°E 37.72 FEET ( SET SPOTTER )  
8" OAK, N58°E 37.28 FEET ( SET SPOTTER )  
2' ± EAST OF CENTERLINE OF N&S ROAD

THIS POSITION NOT ESTABLISHED BY ORIGINAL GOVERNMENT SURVEYORS.  
THIS MONUMENT IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE CORNER.



Signed by [Signature]  
Surveyor's Michigan License No. 20704 ROBERT R. CARR

Date DECEMBER 7, 1998