

# APPROVED

Date 12-9-98 MLL  
**CALHOUN COUNTY**  
**REMONUMENTATION.**

**CALHOUN COUNTY REMONUMENTATION**  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
 CALHOUN COUNTY  
 RECORDED

15 DEC 1998 3:33:03 PM

ANNE B. NORLANDER  
 CLERK - REGISTER OF DEEDS

LIBER **2087** PAGE **919**

Register of Deeds Stamp & File Number

For corners in

<u>Calhoun</u> (County)	Located In:	Corner Code #
Leroy Township	<u>T 3 S R 8 W</u>	<u>F-11</u>
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, William K. Crane, in a field survey on December 3 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

GLO Robert Clark, 1826:

30" W. Ash	S 63° E	34 links
22" W. Ash	S 57° W	39 links

Resurvey, Hodgman, 1885:

Corner dug out in road.	Bisected section lines and set post.	
8" Black Walnut	N 54° E	44 links
12" Sassafras	S 62° E	69 links

Road Commission, R. Watkins, 1961:

Tile iron to be set in 1962 paving.		
30" W. Oak	S 47° E	34.0'
15" Walnut	N 53° E	29.2'
12" Ash	S 31° E	64.2'
6" Ash	S 88° E	64.2'

SURVEY &  
 REMONUMENTATION

MAR 30 1999

SECTION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found iron rod 1' North of fence East and 1.5' East of painted centerline.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced iron rod with standard Calhoun County Remonumentation monument (Berntsen monument with monument box) and is accepted as the best available evidence of the location of the original corner.

Nail and tag in 12" Twin Hickory	N 35° W	60.40'
Nail and tag in 27" W. Oak	S 40° E	33.62'
Nail and tag in 30" Butternut	S 05° E	102.28'
Nail and tag in 36" Maple	S 15° W	144.18'

Signed by William K. Crane  
 William K. Crane, P.S.  
 Surveyor's Michigan License No. 29243

Date December 9, 1998

