

1993

COMMISSION

CALHOUN COUNTY
REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

CLERK-REGISTER
CALHOUN COUNTY, MICH.
ANN F. R. NORLANDER

SEP 1 10 32 AM '93

RECORDED

corners in
CALHOUN

(County)

Located In:

Corner Code #

Public Land Survey

T 3 S R 8 W

G-5

T R

T R

T R

T R

Property Controlling
in Section

S T R

S T R

Miscellaneous

S T R

Property in Sec.

S T R

Register of Deeds Stamp & File Number

Lot No. _____, Recorded Plat _____

Private Claims _____

DONALD J. DAVIS, in a field survey on JULY 23, 1993.

I hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | ● | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

Description of original monument and accessories and/or subsequent restoration:

TILE

2701.3 FEET FROM SOUTH 1/4 POST.

12" TWIN ELM N 04° W 54.5'.

14" ELM S 60° E 96.2'.

26.5' FROM R/W FENCE.

DESTROYED BY ROAD CONSTRUCTION.

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1/2" IRON IN PAVEMENT.

2701.3 FEET FROM SOUTH 1/4 POST.

5' SOUTH OF CENTERLINE OF D DRIVE SOUTH.

CENTERLINE EXTENSION 3 MILE ROAD.

FACE OF UTILITY POLE S 45° W 43.83 FEET.

FACE OF 9" OAK N 20° E 121.61 FEET.

FACE OF 10" ELM S 49° E 68.68 FEET.

RECORDED BY DEKEYSER IN LIBER 1007, PAGE 69, CALHOUN COUNTY RECORDS.

CORNER ACCEPTED AS A FAITHFUL REESTABLISHMENT OF THE ORIGINAL CORNER.

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET BERNTSEN STAINLESS STEEL MONUMENT WITH BRONZE CAP IN MONUMENT BOX AT CORNER.

POWER POLE N 75° E 100.85' NAIL & SPOTTER.

POWER POLE S 50° W 44.30' NAIL & SPOTTER.

16" RED OAK N 30° E 121.80' NAIL & SPOTTER.

8" RED OAK S 70° W 100.60' NAIL & SPOTTER.



Signed by Donald J. Davis

Date August 13, 1993

Surveyor's Michigan License No. 17617