

MAR 30 1999

APPROVED

Date 12-9-98 RRC
CALHOUN COUNTY
REMONUMENTATION.

CALHOUN COUNTY REMONUMENTATION SECTION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>CALHOUN</u>	Located In:	Corner Code #
(COUNTY)		
LERoy TOWNSHIP		
1. Public Land Survey	T <u>3S</u> R <u>8W</u>	<u>G-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

15 DEC 1998 3:40:33 PM

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS

LIBER **2087** PAGE **943**

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, ROBERT R. CARR, in a field survey on JULY 15, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

CORNER COMMON TO SECTIONS 15, 16, 21 AND 22

A. Description of original monument and accessories and/or subsequent restoration:

ORIGINAL CORNER SET BY ROBERT CLARK, D.S. 1826.

HODGMAN, RESURVEY 1885, FOUND STAKE HOLE AT INTERSECTION OF FENCES NORTH AND WEST, NO WITNESS TREES REMAINING, SET POST (TILE).

DON DAVIS, P.S. #17617, UNRECORDED SURVEY, OCTOBER 21, 1974, JOB NO. 594 INDICATES HE USED NORTH 1/4 POST AND NORTHEAST CORNER OF SECTION 21. WITNESSES TO 3/4" IRON FROM RECORDS OF DON DAVIS.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/4" IRON PER DAVIS WITNESSES. THIS IRON APPEARS TO BE ON THE SOUTH SIDE OF A 33 FEET RIGHT-OF-WAY LYING SOUTH OF AND ALONG THE NORTH SECTION LINE. MEASURED NORTH 33 FEET FROM DAVIS 3/4" IRON AND FOUND 3" SOLID TILE SET BY HODGMAN, NO WITNESSES REMAINING, BUT REMAINS OF FENCE WIRE NORTH AND WEST.

REPLACED TILE WITH BERNTSEN MONUMENT IN MONUMENT BOX WITH STONES AROUND.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

BERNTSEN MONUMENT IN MONUMENT BOX WITH STONES AROUND
3/4" IRON, SOUTH 33.46 FEET
15' ± NORTH OF CENTERLINE OF ROAD TO WEST
20" OAK, N57 °W 32.93' (SET SPOTTER)
UTILITY POLE, N32°E 26.23 FEET (SET SPOTTER)
UTILITY POLE, S10°W 30.78 FEET (SET SPOTTER)
4" BASSWOOD, N81°E 61.99 FEET (SET SPOTTER)

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

Signed by [Signature]

Date DECEMBER 7, 1998

Surveyor's Michigan License No. 20704 ROBERT R. CARR

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7							0						
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

