

MAR 30 1999

**APPROVED**

Date 12-9-98 *RRL* CALHOUN COUNTY REMONUMENTATION  
CALHOUN COUNTY LAND CORNER RECORDATION CERTIFICATE  
REMONUMENTATION. Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>CALHOUN</u> (County)	Located In:	Corner Code #
LERROY TOWNSHIP		
1. Public Land Survey	T <u>3S</u> R <u>8W</u>	<u>G-8</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN  
CALHOUN COUNTY  
RECORDED

15 DEC 1998 3:40:55 PM

ANNE B. NORLANDER  
CLERK - REGISTER OF DEEDS

LIBER **2087** PAGE **945**

Register of Deeds Stamp & File Number

I, ROBERT R. CARR, in a field survey on JULY 16, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1/4 CORNER COMMON TO SECTIONS 21 AND 22

A. Description of original monument and accessories and/or subsequent restoration:

ORIGINAL CORNER SET BY ROBERT CLARK, D.S. 1826

HODGMAN, RESURVEY 1885, FOUND STAKE AT INTERSECTION OF FENCES NW 15 LKS.  
FROM STUMP OF BEARING TREE, SET POST (TILE) WITH BRICK UNDER.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1-1/2" PIPE AND BRICK IN KNEE DEEP WATER AT OLD FENCE CORNER.

REPLACED 1-1/2" PIPE WITH 2"X4' PIPE WITH BERNTSEN MONUMENT  
OVER 2" PIPE, CARSONITE WITNESS POST BESIDE.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

BERNTSEN MONUMENT OVER 2"X4' PIPE WITH BRICK AROUND  
CARSONITE WITNESS POST ON NW SIDE  
FENCES RUNNING N&S, E&W AT OLD CORNER POST  
10" ASH, S10°E 30.30 FEET  
10" ASH, S85°E 48.45 FEET  
6" ASH, S25°E 12.20 FEET

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

Signed by *Robert R. Carr*  
Surveyor's Michigan License No. 20704 ROBERT R. CARR

Date DECEMBER 7, 1998

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

