

APPROVED

Date 12-9-98 RKC
CALHOUN COUNTY
REMONUMENTATION.

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

For corners in

Calhoun (County)	Located In:	Corner Code #
Leroy Township		
1. Public Land Survey	T <u>3</u> S. R <u>8</u> W	<u>G-9</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

15 DEC 1998 3:32:51 PM

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS

LIBER **2087** PAGE **918**

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, William K. Crane, in a field survey on December 3 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered; found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

GLO Robert Clark, 1826:

11" W. Oak S 79° W 45½ links
8" W. Oak S 65½° E 16 links

Resurvey, Hodgman, 1885:

Lost. Mr. Burdick says that fences North and South from the corner were set on line when he knew the corners and the road fences also set by the old corner. No other adjoining owners know anything about it. Set post in center of road and on fences North and South.

8" Hickory S 1° E 66 links
2" Maple North 36½ links

SURVEY &
REMONUMENTATION

MAR 30 1999

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found iron rod over tile and rocks as described by Hodgman.

SECTION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced iron and tile with standard Calhoun County Remonumentation monument (Berntsen monument with monument box) and is accepted as the best available evidence of the location of the original corner.

Nail and tag in 14" Hickory	N 47° W	40.45'
Nail and tag in 38" Maple	N 63° E	45.67'
Nail and tag in 38" Maple	S 55° E	46.85'
Nail and tag in 18" Maple	South	24.39'
Capped iron rod	South	33.00'

Signed by William K Crane

Date December 9, 1998

William K. Crane, P.S.

Surveyor's Michigan License No. 29243

