

APPROVED

Date 12-9-98 RLL  
CALHOUN COUNTY  
REMONUMENTATION.

CALHOUN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
CALHOUN COUNTY  
RECORDED

15 DEC 1998 3:33:14 PM

ANNE B. NORLANDER  
CLERK - REGISTER OF DEEDS

LIBER 2087 PAGE 920

Register of Deeds Stamp & File Number

For corners in

Calhoun (County)	Located In:	Corner Code #
Leroy Township	T 3 S R 8 W	G-10
1. Public Land Survey	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, William K. Crane, in a field survey on February 19, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO Robert Clark, 1826:  
13" W. Oak N 77° W 36 links  
8" W. Oak N 64° E 11 links

Resurvey, Hodgman, 1885:  
Found stake and U.S. bearing trees both standing. Set post with brick under.

Chambers, no date:  
173.6' South of face 4" iron fence post  
10" Walnut N 5° W 4.7'  
12" Elm East 3.5'  
14" Hickory S 80° W 46.7'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found traces of ancient fence corner post in stone pile. Excavated 6' x 8' area 4' deep and could not find tile. Established corner at intersection of fences North, South and East at position of old corner post in stone pile.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set standard Calhoun County Remonumentation monument (Berntsen monument) and is accepted as the best available evidence of the location of the original corner.

Nail and tag in 6" Cherry	N 45° W	21.82'
Nail and tag in 12" Cherry	S 80° W	23.60'
Nail and tag in 12" Ash	S 15° W	5.10'
Nail and tag in 4" Cherry	S 55° E	18.77'

Signed by William K. Crane

Date December 9, 1998

William K. Crane, P.S.

Surveyor's Michigan License No. 29243

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

SURVEY &  
REMONUMENTATION

MAR 30 1999

SECTION

